8	Supplying and fixing 50mm GI coller Heavy duty Complete as per specifications.	Nos	220.00	150.00	Rupees One Hundred Fifty Only
9	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for opration on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp Complete as per specifications.	Nos	5.00	10000.00	Rupees Ten Thousand Only
10	Providing and fixing of 50mm G.I pipe 'C' class heavy duty foe erection of submersible pumpset Complete as per specifications.	Mtrs	390.00	402.75	Rupees Four Hundred Two and Seventy Five Paise Only
11	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., Complete as per specifications.	Nos	6.00	475.00	Rupees Four Hundred Seventy Five Only
12	Supplying and fixing 500x500x65mm polished wood board made up not less than 15mm thick plank in front plank one end provided for olding at other end fixing the same of the valve using through bolts and nuts, Complete as per specifications.	Nos	6.00	275.00	Rupees Two Hundred Seventy Five Only
13	Supplying, fixing and wiring heavy duty low voltage capacitors confirming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity Complete as per specifications.	Nos	6.00	350.00	Rupees Three Hundred Fifty Only
14	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring Complete as per specifications.	Nos	6.00	1075.00	Rupees One Thousand Seventy Five Only
15	Supply 1.1 KV class UG cable from nearest BESCOM pole to panel board including earth work and road restoratio 4 core 16 sqmm. Complete as per specifications.	Mtrs	100.00	150.00	Rupees One Hundred Fifty Only
16	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, Complete as per specifications.	Mtrs	100.00	5.00	Rupees Five Only